

## PROJECT FACT SHEET

**Customer:** Adelaide Airport Limited

**Project:** Adelaide Airport

- Project Profile:** Construction of approximately 75000m<sup>2</sup> of new airport terminal facilities, which include:
- Provision of new combined International and Domestic terminal for Adelaide Airport.
  - Integration with existing International terminal building
  - Aircraft aprons and taxiways
  - Peripheral service equipment including aerobridges, aircraft nose in guidance system
  - 4000, 3150, 1600 and 1000 A busduct distribution systems
  - 3 x main distribution boards
  - Back up generator system comprising 2 x 1340kW units, generator distribution board and capability to parallel with ETSA.
  - Apron and car park floodlighting turnstiles and stands
  - Taxiway lighting system
  - Power and lighting
  - Cabling facility for CCTV and security camera systems
  - Communications backbone cabling, cabinets and non-active equipment
  - Temporary power supply
  - Monitored emergency and exit lighting

